

Appendix C


Airport Capacity Design Team Project Summaries¹

The Airport Capacity Design Teams identify and evaluate various corrective actions, which, if implemented, would increase capacity, improve operational efficiency, and reduce delay at the airports under study. The Capacity Teams examine each alternative to determine its technical merit. Environmental, socioeconomic, and political issues are not assessed. These issues will be addressed in other airport planning efforts, like the master planning process.







For those airports where the Airport Capacity Design Team has completed its study, the project summaries and airport layouts contained in this appendix document the capacity improvement alternatives included in the final report. They have not been updated to include any subsequent changes at the airports. For example, the Lambert St. Louis and Memphis International Airport studies were completed in 1988 and there have been significant changes since that time. The current runway plans at these and the other top 100 airports are contained in Appendix D. For those airports where the Capacity Team's analysis is still in progress, the capacity improvement alternatives listed may well change as the study evolves.

The individual recommendations for each airport were developed by the Capacity Teams to be implemented when aircraft operations reached specified levels of demand. For further information on implementation plans, consult the *Airport Capacity Enhancement Plan* for each airport.

1. As of 2-1-93.



Legend

-  Existing Runway
-  Existing Taxiway/Apron
-  Proposed Runway/Runway Extension
-  Proposed Taxiway/Apron/Facility Improvements
-  Buildings
-  Numbers are keyed to alternatives listed in Airport Project Summary

Note: Some buildings/structures may have been removed for clarity.

1,000 ft.
5,000 ft.


Completed

Atlanta-Hartsfield International Airport	C-5
Boston Logan International Airport	C-7
Charlotte/Douglas International Airport	C-9
Chicago Midway Airport	C-11
Chicago O'Hare International Airport	C-13
Detroit Metropolitan Wayne County Airport	C-15
Honolulu International Airport	C-17
Kansas City International Airport	C-19
Los Angeles International Airport	C-21
Memphis International Airport	C-23
Miami International Airport	C-25
Nashville International Airport	C-27
New Orleans International Airport	C-29
Oakland International Airport	C-31
Orlando International Airport	C-33
Philadelphia International Airport	C-35
Phoenix-Sky Harbor International Airport	C-37
(Greater) Pittsburgh International Airport	C-39
Raleigh-Durham International Airport	C-41
Salt Lake City International Airport	C-43
San Antonio International Airport	C-45
San Francisco International Airport	C-47
San Jose International Airport	C-49
San Juan Luis Muñoz Marín International Airport	C-51
Seattle-Tacoma International Airport	C-53
Lambert-St. Louis International Airport	C-55
Washington Dulles International Airport	C-57

Ongoing

Albuquerque International Airport	C-59
(Port) Columbus International Airport	C-61
Fort Lauderdale International Airport	C-63
Houston Intercontinental Airport	C-65
Indianapolis International Airport	C-67

The following design teams were recently initiated and proposed alternatives had not been formulated at press time: Cleveland, Minneapolis, and Eastern Virginia.



Atlanta-Hartsfield International Airport Capacity Design Team Project Summary

Recommendations

Airfield Improvements

1. International concourse
2. Fifth concourse
3. Commuter/GA terminal and runway complex south of Runway 9R/27L
4. Three hold pads/bypass taxiways at end of departure runways
5. Taxiway C parallel to the west of Taxiway D

Facilities and Equipment Improvements


7. Expedite development and installation of wake vortex forecasting and avoidance systems
8. Upgrade NAVAIDs and approach lights on Runway 26R and 27L to Category II
9. Update terminal approach radar
10. Upgrade RVR system to CAT IIIB and ICAO standards
11. Install ASDE-3 with tracking
12. Install touchdown zone lights on Runway 27L
13. Precision Runway Monitor (PRM)
14. CAT III ILS

Operational Improvements

15. Reduce arrival separations to 2.5 nm
16. Enhance traffic management procedures

User Improvements

17. Depeak airline schedules within the hour



Boston Logan International Airport Capacity Design Team Project Summary

Recommendations

Strategy A: Separate the operation of smaller aircraft from large jet aircraft

- A-1 New commuter Runway 14/32, unidirectional (with arrivals only on Runway 32)
- A-2 New commuter Runway 14/32, bi-directional
- A-3 Extend Runway 15L/33R to 3,500' with new taxiway
- A-3a Combine alternatives A-1 and A-3
- A-3b Combine alternatives A-2 and A-3
- A-4/B-4 Removal of noise restrictions to arrivals on Runway 22R
- A-5 400' westward extension of Runway 9 to permit commuters to land on Runway 9 and hold short of Runway 15R during daylight, VFR, dry, conditions
- A-6/D-2 Use of MLS technology for high-angle commuter approaches to avoid wake turbulence, missed approach guidance off Runway 32, and offset approach courses for independent IFR descents into VFR conditions
- A-7 Simultaneous LDA parallel "point-in-space" approaches to Runway 33L, circle to land Runway 4L in marginal IFR (IFR-I) and calm winds

Strategy B: Expand the number of runways on which jets can operate independently under VFR and IFR conditions

- B-1 Extend Runway 27 200' to the east to allow landings holding short of Runway 22L in daylight, VFR, dry conditions
- B-2 Simultaneous approaches to Runways 4R and 4L and Runways 22R and 22L in less than VFR-V conditions
- B-3 Modify ATC procedures to allow simultaneous approaches to Runways 27 and 22L and to Runways 4L and 33L under IFR conditions
- A-4/B-4 Removal of noise restrictions on Runway 4L departures
- A-4a/B-4a Removal of noise restrictions on Runway 4L combined with an extension of Runway 4L to a new taxiway B
- B-5 Side-step approaches from Runway 4R to Runway 4L
- B-6 Use of fan headings for aircraft departing Runways 22L and 22R
- B-7 Use of hold-short procedures under VFR, wet conditions for turbo-jet aircraft on Runway 15R (hold short of 09), 22L (hold short of 27), and 33L (hold short of 4L)

Strategy C: Improve taxiway circulation to expedite ground movement and improve departure sequencing

- C-1 New parallel taxiway between Runways 4L/22R and 4R/22L
- C-2 New south exit parallel taxiway for Runway 27
- C-3 Add fillets at intersection of taxiways D and C with Runway 15R/33L
- C-4 Add staging areas at the ends of Runways 15R/33L, 27, 4R, and 22R, and at the intersection of taxiway G with Runway 33L
- C-5 New taxiway from the end of Runway 27 to the end of Runway 33L
- C-6 Extend taxiway D to Runway 4R/22L

Strategy D: Lower minimum visibility requirements for IFR approaches


- D-1 Install CAT II/III ILS on Runways 15R, 22L, 27 and 33L
- D-2 Use of Microwave Landing System (MLS) technology
- D-3 Reduce minimums to 250' and 3/4 mile on Runway 22L for Category I approaches

Strategy E: Adopt policies which manage demand so that existing and future demand is used more efficiently

- E-1 Increase the percentage of large jet aircraft in the fleet mix
- E-2 Redistribute airline schedules within the hour

Strategy F: Develop more efficient use of the airspace around Logan and Boston Approach Control

- F-1 Improve metering, spacing, and segregation of heavy jets
- F-2 Use WVAS and VAS to decrease separation standards



Charlotte/Douglas International Airport Capacity Design Team Project Summary

Recommendations

Airfield Improvements

1. Build third parallel runway, Runway 18W/36W
 - 1a. Two IFR arrival streams
 - 1b. Three IFR arrival streams (one dependent)
 - 1c. Three IFR independent arrival streams
2. Build fourth parallel runway, Runway 18E/36E
3. Extend Runway 36R further south
4. Extend Taxiway D full Runway 18L/36R length
5. Build angled exits off Runway 18L
6. Build angled exits off Runway 23
7. Construct departure sequencing pads at runway ends
8. Install centerline lights on Runway 5

Facilities and Equipment Improvements


9. Install Category I ILS on Runway 23
10. Install Category II/III ILS on Runway 18R
11. Install Category II/III ILS on Runway 18L
12. Install Category II/III ILS on Runway 36R
13. Install Airport Surface Detection Equipment (ASDE)
14. Expand the Charlotte TRACON and ARTS-III A
15. Acquire the Aircraft Situation Display (ASD)
16. Install Precision Runway Monitor (PRM)
17. Install approach light system on Runway 18L and Runway 23

Operational Improvements

18. Waiver to conduct intersecting runway operations on wet runways
19. Increase Charlotte tower satellite control positions for departures
20. Identify departure restrictions

Other Improvements

21. Improve reliever airports (reduce GA by 50%)
-



Chicago Midway Airport Capacity Design Team Project Summary

Recommendations

Airfield Improvements


1. Runway 31L hold pad
2. Extension to Runway 22L
3. Parallel taxiway between Runways 13R/31L and 13L/31R
4. Runway 22L hold pad
5. Expand apron/gate area
6. Rehabilitation of Runway 13L/31R
7. Reduce arrival minimums for Runways 4R and 31L
8. Commission general aviation Runway 13/31

Air Traffic Control Operational Improvements

9. Intersecting runway operations
10. Silent release departures
11. Dual approach procedures to Runways 31L, 31R, 4L, and 4R
12. Straight-in approach to Runway 22L
13. Meig's instrument approach capability

Research/New Technology Improvements

1. Reduce/eliminate miles-in-trail restrictions
 2. Examine flow control procedures
 3. Reduce aircraft separation criteria
 4. Examine Chicago airspace organization
-



Chicago O'Hare International Airport Capacity Design Team Project Summary

Recommendations

Airfield Improvements


1. Large flow-through aircraft holding areas ("Chicago hold pads")
2. Runway 4R angled exit
3. New Runways 14/32 and 9/27
4. Northward relocation of Runways 9L/27R and 4L/22R
5. Extension to Runway 14L
6. Extension to Runway 22L
7. Southern Runway 9R/27L parallel taxiway
8. Additional Category II/III approach capability

Air Traffic Control Operational Improvements

9. Triple converging instrument approach procedures
10. Intersecting wet runway operations on Runway 14L
11. Independent triple IFR approach procedures

Research/New Technology Improvements

1. Reduce/eliminate miles-in-trail restrictions
 2. Examine flow control procedures
 3. Reduce aircraft separation criteria
 4. Examine Chicago airspace organization
-



Detroit Metropolitan Wayne County Airport Capacity Design Team Project Summary

Recommendations

Airfield Improvements

1. Holding apron and taxiway south
2. Runway and taxiway improvements
 - 2a. High-speed exit taxiway - Runway 21R to Taxiway Y
 - 2b. Extend Taxiway Z to Taxiway V
 - 2c. Construct and expand holding aprons at Runways 3C, 3L, and 3R
 - 2d. Extend inner taxiway parallel to Taxiway H
 - 2e. Construct exit taxiway - Runway 9/27 to Taxiway H
 - 2f. Construct Taxiway S to east GA area
3. Terminal improvements
 - 3a. Terminal expansion
 - 3b. Mid-field terminal
4. Construct independent crosswind Runway 9R/27L
5. Construct independent fourth north/south runway

Facilities and Equipment Improvements


7. Upgrades on Runway 3C
 - 7a. ILS, MLS, and approach lights on existing Runway 3C
 - 7b. RVR for existing Runway 3C
8. ASDE
9. Terminal Doppler Weather Radar (TDWR)
11. RVR and centerline lights on Runway 27
12. Expedite development and installation of wake vortex forecasting and avoidance system
13. Install an airport VOR

Air Traffic Control Improvements

14. Independent converging VFR/IFR approaches to Runways 27 and 21R, hold short of Runway 21R
15. Add controller positions, establish STAR routes, relocate MOTER intersection
16. Use departure corridors
17. Realign Cleveland Center sector airspace
18. Expand tower en route program
19. Reduce arrival longitudinal separation to 2.5 nm
 - 19a. Runway occupancy time reduced 10%
 - 19b. Runway occupancy time reduced 20%
 - 19c. Runway occupancy time reduced 30%

User Improvements

20. Relocate general aviation traffic users
 21. More uniform distribution of scheduled operations within the hour
-



Honolulu International Airport Capacity Design Team Project Summary

Recommendations

Airfield Improvements


1. Effect of new international terminal
2. Relocate and consolidate general aviation (GA) on the south side
3. Relocate commuter terminal
4. Extend Runway 4L/22R to the southwest to 10,000 feet
5. Extend Runway 4R/22L to the southwest to 10,000 feet
6. Extend both Runway 4L/22R and Runway 4R/22L to the southwest to 10,000 feet
7. Construct new GA runway in Keehi Lagoon
8. Extend Runway 8R/26L 1,000 feet
9. Construct new Runway 8C/26C
10. Construct engine run-up pad at east end of Taxiway RA
11. Construct arrival holding area
12. Construct angled exits on Runways 4R, 8L, and 26L

Facilities and Equipment Improvements

13. Install Category II ILS on Runway 8L
14. Install Microwave Landing System (MLS) on Runways 8L, 8R, and 26L

Operational Improvements

15. Increase use of Runway 8R for arrivals
 16. Effect of noise abatement procedures
 17. Distribute traffic more uniformly within the hour
 18. Relocate general aviation (GA) to reliever airports
 - 18a. Relocate 50% of GA
 - 18b. Relocate 100% of GA
 19. Relocate military aircraft
 - 19a. Relocate 50% of military aircraft
 - 19b. Relocate 100% of military aircraft
 - 19c. Increase military to 150% of current level and relocate 100 % of GA
-



Kansas City International Airport Capacity Design Team Project Summary

Recommendations

Airfield Improvements

1. Independent 9,500' Runway 1R/19L
2. Dependent 10,000' parallel Runway 9R/27L
3. Independent 10,000' parallel Runway 18R/36L
4. Dependent 10,000' parallel Runway 18L/36R
5. Add fourth terminal
6. Extend Taxiways B and D to Taxiway H
7. Build holding aprons west of Terminal B
8. High speed exit at A2 for Runway 1L
9. High speed exit at A3 for Runway 19R
10. Extend Taxiway B5 to Runway 19R for GA
11. High speed exit between C5 and C7 for Runway 27R

Facilities and Equipment Improvements


12. CAT III ILS on Runway 1R
13. CAT I ILS on Runway 19L
14. Install ILS/MLS for Runway 27R
15. DME for Runways 1L/19R and 1R/19L
16. RVR for Runway 1R/19L
17. Upgrade Runway 1L ILS to CAT III
18. Benefit of ASDE

Operational Improvements

19. Simultaneous converging instrument approaches
20. Impact of terminal service road
21. Impact of perimeter service road
22. Effect of noise restrictions
23. Effect of ARSA separations within the TCA

User Improvements

24. Uniformly distribute scheduled commercial operations within the hour
 25. Reduce ROTs through pilot and controller education
 26. Reduce longitudinal separations to 2.5 nm
-



Los Angeles International Airport Capacity Design Team Project Summary

Recommendations

Airfield Improvements


1. Construct departure pads (staging areas) at ends of runways
2. Construct new gates west side of Tom Bradley International Terminal (TBIT)
3. Construct 11-gate domestic terminal (east of Sepulveda) and 24-gate international terminal on the west end
4. West end development
 - 4a. Construct 24 remote gates (no terminal) for domestic and international operations
 - 4b. Construct 24-gate passenger terminal for domestic and/or international operations
5. Extend Taxiway K to the east
6. Construct high-speed Taxiway 43
7. Extend Taxiways 48 and 49 to Taxiway F

Facilities and Equipment Improvements

8. Construct new air traffic control tower
9. Upgrade ILS on Runway 25L to CAT III

Procedures Improvements

10. Taxi aircraft versus towing from remote parking areas to gates
 11. Restructure Los Angeles Basin airspace
-



Memphis International Airport Capacity Design Team Project Summary

Recommendations

Airfield Improvements

1. Construct Runway 18E/36E, dual departures
2. Construct Runway 18E/36E, triple departures in VFR-1
3. Construct Runway 18E/36E, triple departures in all weather conditions (waiver required)
4. Extend inner parallel taxiway north to Taxiway V
5. Extend outer Taxiway P north to Taxiway V
6. Extend Runway 18L/36R south
7. Extend Taxiway A from B to BB
8. Large freight ramp, east of Runway 18E, south of Runway 27
9. Extend Taxiway BB to approach end of Runway 36L
10. New crossover Taxiway KK, south of Taxiway HH
11. Terminal expansion
12. Angled exits on Runway 18R/36L (reduce occupancy times by 10%)

Facility and Equipment Improvements


13. CAT II/III ILS on Runway 36R
14. CAT II/III ILS on Runway 36E
15. CAT II/III ILS on Runways 18R, 18L, and 18E
16. Install Airport Surface Detection Equipment (ASDE)
17. Re-route high altitude traffic away from MEM VORTAC

Operational Improvements

18. Reduce longitudinal spacing to 2.5 nm between similar class, non-heavy arrivals
19. Reduce lateral spacing (simultaneous ILS approaches to existing parallels)
20. Small aircraft hold short of Runways 3/21 and 15/33 when landing Runway 27 (regardless of wind)
21. 1.5 nm staggered ILS approach to existing parallels
22. Relief from airspace criteria

User Improvements

23. Reduce small-slow aircraft by 10%; by 25%
 24. Uniformly distribute traffic within the hour
 25. Increase GA forecast by 20%
 26. Relocate Air Guard off airport
-



Miami International Airport

Capacity Design Team Project Summary

Recommendations

Airfield Improvements


1. Dual taxiway around Concourse H (remove 2 end gates)
2. Extend Taxiway L to Runway 9L end
3. Construct new partial dual Taxiway K
4. Develop improved exits for Runway 9L/27R northside
 - 4a. Strengthen/reconstruct Runway 9L/27R
5. Improve Exits M4 and M5 on Runway 9L/27R

Facility and Equipment Improvements

6. CAT II on Runway 9L
7. CAT II on Runway 9R
8. Install touchdown and midpoint RVRs on Runway 9R
10. Glideslope, MALSR, and middle marker on Runway 30
11. ASDE
12. Benefits of MLS
13. Install midpoint and rollout RVRs on Runway 9L

Operational Improvements

14. Independent converging IFR approaches to Runways 12 and 9R
 15. Independent converging IFR approaches to Runways 27R and 30
 16. 2.5 mile in-trail longitudinal approach separation (IFR)
-



Nashville International Airport Capacity Design Team Project Summary

Recommendations

Airfield Improvements


1. Relocate Runway 2C and extend to 8,000 ft.
2. Extend Runway 13 to the northwest
3. Extend Runway 2L 1,300 ft. or more to the south
4. Improve terminal taxiways and ramp
 - 4a. Extend Taxiway I
 - 4b. Extend Taxiway B
 - 4c. Construct dual lane at Taxiway T-4
 - 4d. Construct dual lane at Taxiway T-6
5. Construct new Runway 2E/20E 1,500 to 3,000 ft. east of existing Runway 2R/20L
 - 5a. Less than 2,500 ft. east of Runway 2R/20L
 - 5b. 2,500 ft. east of Runway 2R/20L (dependent)
6. Extend existing Runway 20L 1,000 ft. north
7. Extend existing Runway 2R 1,000 ft. south
8. Construct holding (departure sequencing) pads on all runway ends (bypass capability)
9. Construct taxiway from GA area to Runway 31 departure end
10. Construct crossover taxiway from ramp to Runway 20L
11. Construct connecting taxiway from Concourse D to Runway 2R/20L
12. Construct new exit for commuters east off Runway 20R at 5,000 ft.
13. Expand existing terminal
14. Round off fillet at Taxiway C and Runway 2L

Facilities and Equipment Improvements

15. Upgrade ILS on all existing and future runways
16. Install wake vortex advisory system

Operational Improvements

17. Encourage GA use of reliever airports
 18. Conduct IFR dependent converging approaches to Runways 13 and 20L
 19. Conduct an airspace capacity design project and re-structure terminal and en route airspace
 - 19a. Evaluate airspace restrictions
 - 19b. Revise low-altitude airway structure
 20. Establish a terminal control area (TCA)
-



New Orleans International Airport Capacity Design Team Project Summaries

Recommendations

Airfield Improvements


1. Construct new general aviation (GA) complex and east/west taxiway on north side
2. Convert north parallel east/west taxiway into new commuter/GA Runway 10L/28R
 - 2a. Construct parallel taxiway north of Runway 10L/28R
3. Construct new air carrier runway
 - 3a. Construct dependent non-parallel Runway 1L/19R
 - 3b. Construct independent parallel Runway 1L/19R
 - 3c. Construct independent parallel Runway 10S/28S
4. Construct east/west dual taxiway south of Runway 10R/28L
5. Construct new international and domestic gates and renovate one gate on Concourse C
6. Construct new Concourse E (20 gates) for air carrier operations
7. Develop air cargo complex and associated aprons
 - 7a. Develop Area 1 — Stage I east air cargo apron
 - 7b. Develop Area 2 — existing and south-of-existing GA areas
 - 7c. Develop Area 3 — Stage II east air cargo apron
 - 7d. Develop Area 4 — west air cargo apron
8. Construct perimeter road
9. Study requirement for new airport

Facilities and Equipment Improvements

- 10a. Move VORTAC from current location in lake, possibly to New Orleans International Airport
- 10b. Install additional VOR
11. Construct new airport traffic control tower (ATCT)

Operational Improvements

12. Effects of noise constraints
 13. Develop and implement converging instrument approaches
 - 13a. “TERPS plus 3” approach procedure to Runways 10R and 19L and Runways 10R and 1R
 - 13b. Dependent IFR approaches to Runways 10R and 19L and Runways 10R and 1R
 14. Use 2.5 nm spacing between similar class, non-heavy aircraft
 15. Conduct an airspace capacity design project and restructure terminal airspace
 16. Study effects of existing public-use heliport
 17. Enhance GA reliever airports
 - 17a. Reduce GA traffic by 25%
 - 17b. Reduce GA traffic by 50%
 - 17c. Reduce GA traffic by 75%
-



Oakland International Airport Capacity Design Team Project Summary


Recommendations

Airfield Improvements

1. Construct taxiway from southeast corner of terminal to Runway 29 approach threshold
2. Build taxiway parallel to Runway 27L
3. Add taxiway between north and south complexes
4. Convert Taxiway 1 to air carrier Runway 29 and add parallel taxiway
5. Enlarge staging pads at entrances to Runway 11/29
6. Construct additional angled exit off Runway 11
7. Build penalty box on south side of approach end of Runway 29

Facilities and Equipment Improvements

8. Install MLS on Runways 29 and 27
 9. Install a non-directional beacon approach to Runway 29
-



Orlando International Airport Capacity Design Team Project Summary

Recommendations

Airfield Improvements

1. Extend Taxiway C to threshold of Runway 36R
2. Construct new heliport
3. Construct north crossfield taxiway
- 4a. Construct new Taxiway B9 from Runway 36R to Runway 36L
- 4b. Construct new Taxiway B9 from Taxiway A to threshold of Runway 36L
5. Construct staging areas on all runways
6. Construct fourth runway and associated taxiways

Facilities and Equipment Improvements


7. Install VOR at OIA
- 8a. Install CAT III ILS on Runway 18R
- 8b. Install CAT III ILS on all runways
9. Install ASDE
10. Install PRM

Operational Improvements

11. Implement ramp control by users
12. Implement triple parallel approaches (four-runway configuration using PRM)
13. Modifications to terminal airspace
14. Restructure airways
15. Use ground crossovers versus air crossovers
16. Segregate GA and helicopter operations from turbojets

User Improvements

17. Encourage GA use of alternative airports by providing new east and west reliever airports



Philadelphia International Airport Capacity Design Team Project Summary

Recommendations

Airfield Improvements


1. Extend Runway 17/35 600 ft. to the north
2. Construct new 5,000-ft. commuter Runway 8/26 3,000 ft. north of Runway 9R/27L
3. Relocate Runway 9L/27R (laterally) 400 ft. to the south with associated parallel and apron taxiways
4. Relocate Runway 9L/27R (longitudinally) 2,735 ft. to the west
5. Relocate Runway 9R/27L (longitudinally) 1,000 ft. to the east

Facilities and Equipment Improvements

6. Install localizer directional aid (LDA) on Runways 9L and 27L
 - 6a. LDA approach to Runway 27L with ILS arrivals on Runway 27R
 - 6b. LDA approach to Runway 9L with ILS arrivals on Runway 9R
7. Install Precision Runway Monitor (PRM)

Operational Improvements

8. Allow restricted air carrier use on Runway 17/35 with arrivals on Runway 35 and departures on Runway 17
 9. Implement preferential taxiway routing
 10. Conduct dependent instrument approaches to Runways 27L and 17
 11. Conduct dependent instrument approaches to Runways 27R and 17
 12. Implement a steep-angle MLS approach to Runway 27L
 13. Conduct an airspace capacity design project and re-structure terminal airspace
 - 13a. Remove departure fix restrictions
 - 13b. Install terminal ATC automation (TATCA) enhancements
-



Phoenix-Sky Harbor International Airport Capacity Design Team Project Summary

Recommendations

Airfield Improvements

1. Construct new Runway 8S/26S south of Runway 8R/26L with associated taxiways
2. Construct holding aprons at two runway ends
3. Widen fillets at Taxiways C5 and C7 off of Runway 8R/26L
4. Holding area southeast of Terminal 3
5. New angled exit off of Runway 8R/26L to Taxiway C
6. New angled exit off of Runway 8S/26S to Taxiway D
7. Second midfield crossover Taxiway Y adjacent to Taxiway X
8. Crossover Taxiway W and associated taxiways at approach ends of Runway 26R and Runway 26L
9. Crossover Taxiway Z from Taxiways B3 to C3
10. Construct Terminal 4 and remove Terminal 1
- 11a. Extend Taxiway A to end of Runway 26R
- 11b. Extend Taxiway D to end of Runway 26L
12. Complete northside taxilane (parallel to and north of Taxiway C)
13. Relocation of 161st Air Refueling Group

Facilities and Equipment Improvements


14. TVOR/VORTAC (Carefree) in northern valley
15. ILS (CAT I) for Runway 26R
16. Precision approach for Runway 8L
17. Precision approach for Runway 8S/26S
18. Potential benefits of MLS at Sky Harbor
19. VORTAC near airport

Operational Improvements

20. Reduce in-trail separations to 2.5 nm
21. Reduce runway occupancy times
22. IFR dependent parallel approaches
23. IFR independent parallel approaches
24. Segregate fast and slow aircraft
25. Reduce arrival to intersection departure separation
26. Reduce in-trail departure restrictions to allow simultaneous departures
27. Reduce noise restrictions to utilize special turboprop corridors

User Improvements

28. Uniformly distribute scheduled commercial operations within the hour
 29. Provide attractive alternative facilities for GA at other airports
 30. Pilot education for reduced runway occupancy times
-



Greater Pittsburgh International Airport Capacity Design Team Project Summary

Recommendations

Airfield Improvements

Runway Extension

1. Extend Runway 10C/28C 2,000 feet west

One New Runway

2. Build 8,500 foot independent south parallel runway 4,300 feet south of Runway 10R/28L
3. Build 8,200 foot north parallel runway 1,000 feet north of Runway 10L/28R
4. Build 8,500 foot dependent south parallel runway 3,100 feet south of Runway 10R/28L
5. Build 9,000 foot crosswind Runway 14R/32L 8,700 feet west of Runway 14/32

Two New Runways

6. Build north and south parallel runways
7. Build two south parallel runways, 3,100 and 4,300 feet south of Runway 10R/28L
8. Build south parallel and crosswind runways

Terminal Area Improvements


9. Add new gates to northwest finger of new Midfield Terminal and improve Taxiway H to Taxiway R
10. Add new gates to southwest finger of new Midfield Terminal and improve Taxiway K from Taxiway W to A

Facilities and Equipment Improvements

11. Upgrade Runway 10R to CAT II/III ILS
12. Install Precision Runway Monitor (PRM)

Operational Improvements

13. Conduct an airspace capacity design project and re-structure terminal airspace
-



Raleigh-Durham International Airport Capacity Design Team Project Summary

Recommendations

Airfield Improvements


1. Relocate Runway 5R/23L 1,200 ft. southeast and extend to 9,000 ft. in length
2. Construct new 8,000 ft. third parallel Runway 5W/23W
Runway 5W/23W
 - 2a. 1,000 to 2,400 ft. from Runway 5L/23R
 - 2b. 2,500 ft. from Runway 5L/23R
 - 2c. 3,000 to 4,300 ft. from Runway 5L/23R**Runway 5E/23E**
 - 2d. 8,000 ft. runway 1,000 to 2,400 ft. from relocated Runway 5R/23L
 - 2e. 8,000 ft. runway 2,500 ft. from relocated Runway 5R/23L
 - 2f. 8,000 ft. runway 3,000 to 4,300 ft. from relocated Runway 5R/23L
3. Construct new fourth parallel Runway 5E/23E (assumes Runway 5W/23W in place)
 - 3a. Triple independent/dependent arrivals
 - 3b. Triple independent arrivals
4. Construct dual parallel taxiway near feeder Taxiway E
5. Construct taxiway from new cargo complex to Runway 5R/23L
6. Construct full-length dual parallel taxiways for Runway 5R
7. Construct angled exits on Runway 5L/23R
8. Expand holding and sequencing pads and bypass taxiways on Runway 5R/23L and all future runways

Facilities and Equipment Improvements

9. Install CAT II/III ILS on existing and future runways
10. Install runway visual range (RVR) on Runway 23L and future runways
11. Install wake vortex advisory system
12. Install airport surface detection equipment (ASDE)

Operational Improvements

13. Implement staggered approaches with 1.5 nm separation
 14. Implement independent approaches to existing runways (Precision Runway Monitor (PRM))
 15. Implement 2.5 nm spacing between similar class, non-heavy aircraft arrivals in IFR
 16. Establish a terminal control area (TCA)
 17. Study noise abatement procedures
 18. Conduct an airspace capacity design project and restructure terminal and en route airspace
-



Salt Lake City International Airport Capacity Design Team Project Summary

Recommendations

Airfield Improvements

1. Construct a parallel runway to the west with independent IFR capability (CAT III ILS on both ends)
2. Taxiway to Delta Air Lines hangar
3. Relocate tower
4. Revise taxiway exit layout
5. Construct staging areas for Runway 16R/34L at runway entrances
6. Terminal expansion
7. Extend Taxiways S and T to west boundary of the terminal ramp
8. Rehabilitate Taxiways X and Y
9. Improve aircraft access to cargo facilities

Facilities and Equipment Improvements


10. CAT I ILS on Runway 34R
11. LDA approach to Runway 34R
12. CAT III ILS on Runway 16R
13. Install Precision Runway Monitor (PRM)
14. Install Microwave Landing System (MLS)
15. Install runway visual range (RVR) equipment on Runway 34R
16. Install Airport Surface Detection Equipment (ASDE)
17. Install taxiway centerline lights

Operational Improvements

18. Make Bonneville routing one-way
19. Reduce in-trail arrival separation standard to 2.5 nm (like class aircraft only)
20. IFR independent converging approaches

User Improvements

21. Reduce runway occupancy times through pilot education (10%, 20%, or 30% runway occupancy time reduction)
 22. Improve reliever airports (reduce general aviation operations by 10%, 20%, or 30%)
 23. Delta Air Lines ramp control tower
-



San Antonio International Airport Capacity Design Team Project Summary

Recommendations

Airfield Improvements


1. Construct new Runway 12N/30N northeast of Runway 12R/30L
 - 1a. Construct independent air carrier length Runway 12N/30N
 - 1b. Construct dependent air carrier length Runway 12N/30N
 - 1c. Construct independent regional air carrier/general aviation (GA) Runway 12N/30N
2. Extend Runway 12L/30R to air carrier length and operate without noise restrictions
 - 2a. Extend Runway 12L/30R and operate with noise restrictions
3. Construct independent air carrier Runway 3L/21R
4. Construct new and improve existing taxiway system to extended Runway 12L/30R
 - 4a. Widen and strengthen Taxiway K and extend to Taxiway R
 - 4b. Improve Taxiways M and P and part of Taxiway N near end of Runway 30L
 - 4c. Construct new diagonal Taxiway J1 at end of Runway 12R
5. Widen Taxiway F and Taxiway E west to ramp at end of Runway 3
6. Construct new Taxiway N1 at end of Runway 21
7. Construct new or extend existing taxiway system to new Runway 12N/30N and extended Runway 12L/30R
8. Provide shoulders for Taxiway G to accommodate four-engine jets
9. Construct holding pads at departure ends of Runways 12R, 3, and 30L
10. Construct holding pads at departure end of Runway 21
11. Expand Terminal to 60 gates
 - 11a. Construct Taxiway H1 to support terminal expansion
12. Expand east cargo ramp
13. Construct arrival holding areas
14. Improve exit turnoffs for existing runways
15. Provide stabilized shoulders for Runway 12R/30L

Facilities and Equipment Improvements

16. Install doppler radar for wind shear detection
17. Install Precision Runway Monitor (PRM)
18. Install Airport Surface Detection Equipment (ASDE)
19. Upgrade ILS on Runway 12R to Category III
20. Install Category II/III ILS on Runway 12N and Category I ILS on Runway 30N with associated approach light system (ALS) and runway visual range (RVR)
21. Install Category I ILS on extended Runway 12L/30R with associated ALS and RVR
22. Install Microwave Landing System (MLS) on Runway 21
23. Install Localizer Directional Aid (LDA) on Runway 12L/30R
24. Install dual Runway Visual Range (RVR) on Runway 3

Operational Improvements

25. Reduce in-trail arrival separations to 2.5 nm
 26. Segregate traffic on runways
 - 26a. Segregate by aircraft type
 - 26b. Segregate by arrivals and departures
 27. Install Wake Vortex Advisory System (WVAS) (existing configuration)
 - 27a. Install WVAS (with Runway 12L/30R extension)
 28. Relocate general aviation (GA)/fixed base operator (FBO) areas to northwest side of Runway 12L
 29. Relocate non-air carrier operations
 - 29a. Relocate 25% of non-air carrier operations
 - 29b. Relocate 50% of non-air carrier operations
 30. Distribute traffic more uniformly
 31. Conduct an airspace capacity design project and re-structure San Antonio area airspace
 32. New commercial airport planning
-



San Francisco International Airport Capacity Design Team Project Summary

Recommendations

Airfield Improvements

1. Create holding areas near Runways 10L, 10R, 1R, and 28R
2. Improve noise barrier for Runway 1R
3. Extend Runways 19L and 19R
4. Extend Runways 28L and 28R
5. Construct independent parallel Runway 28
6. Extend Taxiway C to threshold of Runway 10L
7. Create high speed exit from Runway 10L between Taxiways L and P
8. Extend Taxiway T to Taxiway A

Air Traffic Control Improvements


9. Expand visual approach procedures
10. Offset instrument approach to Runway 28R
11. Use staggered 1-mile divergent IFR departures on Runways 10L and 10R

Facilities and Equipment

12. Install Microwave Landing System (MLS) on Runways 28 and 19

User Improvements

13. Taxi aircraft across active runways instead of towing
 14. Distribute airline traffic more evenly among three airports
 15. Distribute traffic uniformly within the hour
 16. Divert 50% general aviation to reliever airports
-



San Jose International Airport Capacity Design Team Project Summary

Recommendations

Airfield Improvements


1. Create staging area at Runway 30L
1. Create staging area at Runway 30R
2. Extend and upgrade Runway 11/29
 - 2a. Extension of Runway 30R
3. Create angled exits for Runway 12R

Facilities and Equipment Improvements

4. Promote use of reliever ILS training facility
5. Install MLS on Runway 30L

Air Traffic Control Improvements

6. Implement simultaneous departure with Moffett Field
-



San Juan Luis Muñoz Marín International Airport Capacity Design Team Project Summary

Recommendations

Airfield Improvements

1. Construct new north/south taxiway complex at the west end
 - 1a. Single one-way taxiway
 - 1b. Two-directional taxiway
2. Expand existing north/south taxiway to provide two-directional capability
3. Extend Taxiway S
4. Construct new ramp area on south side of airport
5. Construct new/improve existing exits on Runways 8 and 10
6. Expand existing Taxiways S and H to dual taxiways adjacent to north and south ramps
7. Construct holding pads (staging areas) on Runways 8 and 10
 - 7a. With three hold positions
 - 7b. With five hold positions
8. Construct new international passenger terminal

Facilities and Equipment Improvements


9. Upgrade VOR to include doppler
10. Construct new air traffic control tower
11. Install wake vortex advisory system
12. Install terminal ATC automation (TATCA) enhancements
13. Install improved approach aids on Runway 26
 - 13a. Install Precision Approach Path Indicator (PAPI)

Operations Improvements

14. Implement improved oceanic separations (no fix restrictions)
15. Use 2.5 nm separations on final approach
16. Unrestricted use of Runway 10

User Improvements

17. Remove military operations
 18. Enhance general aviation (GA) reliever airports and reduce GA activity by 50%
-



Seattle-Tacoma International Airport Capacity Design Team Project Summary

Recommendations

Improvements to Existing Airfield

1. Improved exit and taxiway construction
2. Reduce in-trail spacing to 2.5 nm
3. CAT I ILS on Runway 16L (IFR-1)
4. LDA approach to Runway 16L/34R and ILS to Runway 16R/34L
5. Noise abatement effect on departures
6. Install wake vortex advisory system

New Runway Improvements

Commuter Runway

7. Commuter Runway 17C/35C (converted Taxiway D)
8. LDA to Runways 17C/35C and ILS to Runway 16L/34R
9. Install wake vortex advisory system

Dependent Runway


10. Air carrier (dependent) Runway 16W/34W
11. LDA approaches to Runway 16W/34W
12. CAT I ILS on Runway 16W (IFR-1)
13. CAT II ILS on Runway 16W (over CAT I)
14. CAT I ILS on Runway 34W (IFR-1)
15. Staggered approaches to Runways 16L & 16W and 34R & 34W - 2.0 nm stagger
16. Staggered approaches to Runways 16L & 16W and 34R & 34W - 1.5 nm stagger
17. Operate Runway 16R/34L as primary runway versus Runway 16L/34R with Runway 16W/34W
18. Install wake vortex advisory system

Independent Runway

19. Air carrier (independent) Runway 16W/34W
20. CAT II on Runway 16W (only)

Demand Management

21. Uniformly distribute scheduled commercial operations
-



Lambert-St. Louis International Airport Capacity Design Team Project Summary

Recommendations

Airfield Improvements

1. New runway parallel to Runway 12L/30R
 - 1a. Alternate 1: new independent commuter runway 2,500 ft. from Runway 12L/30R
 - 1b. Alternate 2: new dependent commuter runway 1,400 ft. from Runway 12L/30R
 - 1c. Alternate 3: new independent air carrier runway parallel to Runway 12L/30R
2. Convert Taxiway F to VFR Runway 13/31
3. Angled exits on Runway 12L/30R
4. Taxiway extensions
 - 4a. Extend Taxiway A south to end of Runway 30L
 - 4b. Extend Taxiway P from Taxiway C to Taxiway M
 - 4c. Extend Taxiway C from Taxiway F to end of Runway 24
5. Realign Taxiway B off Taxiway A to Runway 12R/30L
6. Establish queuing areas to various runway ends
7. Relocate cargo area
8. Relocate mid coast aviation to northeast

Facilities and Equipment Improvements


9. Install marker lights and parking lanes in center field remote holding area
10. Install wake vortex advisory system
11. Install CAT III ILS to reduce approach minima on Runways 12L and 12R
12. IFR approaches with additional instrumentation on Runway 6
13. IFR approaches with additional instrumentation on Runway 24
14. LDA approaches support
 - 14a. Equipment installation on Runway 30L
 - 14b. Equipment installation on Runway 12L
15. Install light systems at taxiway and runway intersections
16. Install ASDE

Operational Improvements

17. Reduce IFR parallel approach stagger to 2 nm
18. Reduce IFR in-trail separations to 2.5 nm
19. Converging IFR approaches to
 - 19a. Runways 6 and 30R
 - 19b. Runways 6 and 30L
20. Converging IFR approaches to
 - 20a. Runways 24 and 30R
 - 20b. Runways 24 and 30L
21. Simultaneous approaches to ILS Runway 30R, LDA Runway 30L, and ILS Runway 24

User Improvements

22. Change fleet mix
 - 22a. Relocate GA 25%
 - 22b. Relocate GA 50%
 - 22c. Relocate GA 75%
 23. Distribute scheduled commercial operations within the hour
 24. Relocate Air National Guard
-



Washington Dulles International Airport Capacity Design Team Project Summary

Recommendations

Airfield Improvements

1. Construct Runway 1W/19W 3,500 ft. west of Runway 1L/19R
2. Construct Runway 12R/30L south of Runway 12/30
3. Widen turnback fillets on Runway 1L (at Exits W-3, W-5)
4. Widen turnback fillets on Runway 19L (at Exits E-6, E-8) (not pictured)
5. Complete construction of east/west Taxiway R-2
6. Add GA exits to Runways 19R (north of Exit W-3) and 19L (north of Exit E-3)
7. Extend Runway 12/30 southeast and enlarge Runway 30's holding pads
8. Add Runway 1R holding pad and extend Taxiway E-2 south (to south of Exit E-7)
9. Runway 19R staging improvements: extension of Taxiway W-2 north, Runway 19R holding pad, and Runway 19R bypass taxiway
10. Add midfield ramp
11. Add centerfield north/south taxiway
12. Midfield Terminal — Phase 1A (24 gates)
13. Midfield Terminal — Phase 1B (48 gates)
14. Add east/west Taxiway R-3, south of R-2, with 2 north/south stubs
15. Additional FBO, east of Runway 19R threshold

Facilities and Equipment Improvements


16. Touchdown RVR and touchdown zone lights on Runway 1L
17. Touchdown RVR and centerline lights on Runways 12 and 30 and touchdown zone lights on Runway 12

Operational Improvements

18. Simultaneous ILS approaches to existing parallel runways
19. Simultaneous converging instrument approaches to Runways 12 and 19R or 12 and 19L
20. 2.5 nm longitudinal spacing inside outer marker (between similar class, non-heavy arrivals)

User Improvements

21. Redistribute traffic more uniformly within the hour
 22. Improve reliever airports: reduce small-slow aircraft by 25%; by 50%
-



Albuquerque International Airport Capacity Design Team Project Summary

Proposed Alternatives

Airfield Improvements


1. Extend, widen, and strengthen Runway 3/21 and operate as a 10,000-foot air carrier runway
2. Construct new and improve existing taxiways and exits
 - 2a. Widen and strengthen Taxiway A along full length, parallel to and north of Runway 8/26
 - 2b. Construct 4,000 ft. Taxiway AA parallel to and north of Taxiway A, from Runway 17/35 to Exit A4
 - 2c. Improve or add angled (high-speed) exits on Runway 8/26 to Taxiway A
3. Extend Runway 12/30 to the southeast and operate as a 10,000-foot air carrier runway
4. Construct new parallel air carrier runway south of Runway 8/26
 - 4a. Operate as a dependent IFR runway
 - 4b. Operate as an independent IFR runway
5. Construct holding areas for Runway 8/26

Facilities and Equipment Improvements

6. Install ILS on Runway 3
7. Install CAT II/III ILS on Runway 8
8. Install ILS on Runway 35
9. Install TVOR/DME
10. Install ILS on Runway 30

Operational Improvements

11. Benefit of MLS procedures to Runway 26
 12. Reduce in-trail separations to 2.5 nm from 3 nm in IFR
 13. Evaluate impact of noise abatement procedures
 14. Implement dependent converging approaches with ILS on Runways 3 and 8
 15. Enhance GA reliever airports
 16. Terminal expansion (added gates)
 17. Assign designated areas for civil helicopters
-



1,000 ft

5,000 ft

New or Additional Runup/Hold Pads

Buildings to be Removed

Port Columbus International Airport Capacity Design Team Project Summary

Proposed Alternatives

Airfield Improvements


1. Relocate and extend Runway 10L/28R
 - 1a. Extend Runway 10L 1,000 ft. east
 - 1b. Extend Runway 28R 1,000 ft. west
 - 1c. Extend Runway 10L/28R to 8,000 ft.
2. Build a third parallel runway 800 ft. south of Runway 10L/28R; use existing Runway 10L/28R as a departure runway; build fourth runway 600 ft. north of Runway 10L/28R
3. Improve or add angled exits
4. Expand passenger terminal
 - 4a. Add 10 gates on west side
 - 4b. Add 6 gates on east side
 - 4c. Add 10 additional gates
5. Relocate west end of Taxiway B
6. Build north parallel taxiway for Runway 10L/28R
7. Build crossover taxiway at west end between Runway 10L/28R and Runway 10R/28L
 - 7a. Build one-way taxiway
 - 7b. Build two-way taxiway
8. Build bypass taxiway on east side
9. Build run-up pads at all air carrier runway ends
10. Reconstruct/strengthen Taxiway G south of Runway 10R/28L
11. Build blast area for engine runups north and south of Runway 28L

Facilities and Equipment Improvements

12. Install CAT I ILS on Runways 10L/28R and 10R/28L (with centerline lights)
13. Install CAT II ILS
14. Install Microwave Landing System (MLS) on Runway 28R
15. Install Precision Runway Monitor (PRM)
16. Install Airport Surface Detection Equipment (ASDE)
17. Install Distance Measuring Equipment (DME) on Runway 28L
18. Build new Airport Traffic Control Tower (ATCT)
19. Install additional NAVAIDS

Operational Improvements

20. Impact of noise reduction procedures
 - 20a. Effect of Stage III aircraft
 - 20b. Unrestricted use Runway 10L/28R
 21. Provide 1.5 nm staggered approaches to Runways 10R/28L and 10L/28R in IFR
 22. Provide 2.5 nm in-trail separations between similar class aircraft
 23. Redistribute traffic more uniformly within the hour
 24. Enhance GA reliever airports
 25. Conduct airspace capacity design project and restructure area airspace
-



Fort Lauderdale International Airport Capacity Design Team Project Summary

Proposed Alternatives

Airfield Improvements


1. Extend Runway 9R/27L— 6,000 ft. long, 150 ft. wide, and CAT I ILS
 - 1a. 2 nm stagger in IFR
 - 1b. 1.5 nm stagger in IFR
 - 1c. Simultaneous parallel IFR approaches (with PRM)
 - 1d. Simultaneous approaches and 2.5 nm minimum in IFR (1c and 16)
2. Extend Runway 9R/27L — 10,000-ft. long, 150 ft. wide, and CAT I ILS
 - 2a. 2 nm stagger in IFR
 - 2b. 1.5 nm stagger in IFR
 - 2c. Simultaneous parallel IFR approaches (with PRM)
 - 2d. Simultaneous approaches and 2.5 nm minimum in IFR (2c and 16)
3. Extend Runway 9R/27L to 10,000 ft; operate under restricted use
 - 3a. With 2 nm stagger in IFR
 - 3b. Simultaneous parallel IFR approaches (with PRM)
4. Improve angled exits
 - 4a. Widen fillets at Exit Q on Runway 9L
 - 4b. Widen angled exit Runway 27R, south, at Taxiway F
5. Add or expand run-up pads to stage departures
6. Taxiway and exit improvement package
7. Expand terminal (international and air carrier)

Facilities and Equipment Improvements

- 8a. CAT I ILS on Runway 9R
- 8b. CAT I ILS on Runway 27L
9. CAT I ILS on Runway 31
10. CAT II/III ILS on Runway 27R
11. Precision Runway Monitor (PRM) — when south runway extended
12. Upgrade FLL radar — commission ASR-9
13. Relocate TVOR/VOR off Airport
14. Vortex Advisory System (VAS)
15. Low Level Wind Shear Alert System (LLWAS)

Operational Improvements

16. Reduce minimum in-trail separations to 2.5 nm
 17. Reduce stagger to 1.5 nm in IFR
 18. Unrestricted use of Runway 13/31 for departures (cost of noise restrictions on use of Runway 13/31)
 19. Unrestricted use of Runway 13 (impact of Ft. Lauderdale Executive Airport (FXE) operations)
 20. Conduct a study of South Florida airspace and implement airspace management
 21. Increase/enhance reliever airports
 22. Redistribute traffic more uniformly within the hour
-



Houston Intercontinental Airport Capacity Design Team Project Summaries

Proposed Alternatives

Airfield Runway Improvements

- 1a. Extend, widen, and strengthen Runway 14R/32L for air carrier departures, with arrivals on Runways 26L and 27R
- 1b. Construct air carrier Runway 8C/26C 1,200 ft. north of Runway 8R/26L
- 1c. Construct air carrier Runway 8L/26R to support triple independent approaches
- 1d. Construct air carrier Runway 9C/27C 1,200 ft. south of Runway 9L/27R
- 1e. Construct both Runway 8L/26R and Runway 9C/27C
- 1f. Construct both Runway 8L/26R and new air carrier Runway 9R/27L to support quadruple independent approaches
- 1g. Construct both Runway 8C/26C and Runway 9C/27C

Airfield Taxiway Improvements


- 2a. Add independent taxiway and departure holding pads to existing Runway 14R/32L
 - 2a.1. With current runway assignments
 - 2a.2. As air taxi/commuter runway only
- 2b. Add high speed exit off Runway 14R
- 2c. Extend Taxiway WA from Taxiway WL to Taxiway WB to allow two-way traffic
- 2d. Extend Taxiway WH to Taxiway SA (bridging over JFK Boulevard)
- 2e. Widen Taxiways NJ and NK to allow two-way traffic
- 2f. Extend Mickey LeLand Memorial International Airlines Building (IAB) Ramp
- 2g. Extend North Ramp to connect Terminals B and C
- 2h. Add dual taxiway at South Terminal Ramp (bridging over JFK Boulevard)
- 2i. Add high speed exits at Taxiways SG and SH
- 2j. Add second crossfield taxiway at midfield to provide two-way flow
- 2k. Construct cargo gate and taxiway complex north side
- 2l. Construct new terminal

Facilities and Equipment Improvements

- 3a. Upgrade to CAT III ILS on Runway 27R

Operational Improvements

- 3b. Conduct dependent IFR approaches to Runways 14L & 9L and 14L & 26
 4. Distribute traffic more uniformly during peak periods
 5. Construct new reliever airport on west side
 6. Add a public-use heliport at IAH
 7. Construct additional airline hub at Terminal B
-



Indianapolis International Airport Capacity Design Team Project Summaries

Proposed Alternatives

Airfield Improvements

0. Replace runway 5L/23R
1. Build third dependent runway 800 ft. east of Runway 5L/23R
2. Build third independent northeast/southwest runway (with Precision Runway Monitor (PRM))
3. Build a second northwest/southeast dependent runway 800 ft. northeast of Runway 14/32
4. Build both third dependent runway and fourth independent northeast/southwest runway (combines 1 and 2)
5. Add angled exits to Taxiway F for future Runway 5L/23R
6. Add angled exits Runway 14/32
7. Build departure sequencing pads for Runways 5L and 5R
8. Build dual taxiway system for future Runway 5L/23R
9. Build northeast crossover Taxiway C
10. Build fourth crossfield taxiway at southwest end
11. Add angled exits for Runway 5R/23L

Facilities and Equipment Improvements

12. Add centerline lights Runway 14/32
13. Install touchdown runway visual range (RVR) Runway 14
14. Install Airport Surface Detection Equipment (ASDE) radar
15. Install surface movement guidance and control system
16. Install Aircraft Situation Display (ASD)
17. Install approach light system (ALSF-2) on Runway 14/32
18. Upgrade low-level wind shear advisory system
19. Upgrade RVR to CAT IIIB and ICAO standards in Runways 5R and 5L
20. Install doppler weather radar

Operational Improvements

21. End-fire glide slope for Runways 23R and 14
 22. Reduce in-trail separations to 2.5 nm
 23. Develop dependent converging approaches
 24. Effect of noise restrictions
 25. Reduce runway occupancy times
 26. Continue enhancement of reliever airports to accommodate a reduction in small/slow aircraft operations at IND
-

