

Flight Procedures Cover Page	Task Action: FLIGHT CHECK	Task Type: IAP	Estimated Chart Date: 11/27/2025	APWS Task ID: 2B1E42BBCAB2453A9B92376B64F8C03C	APWS Project ID: 519F4508F3604FECB5F0A0AE93A49F38
Procedure: RNAV (GPS) RWY 10 AMDT 2		Enroute: NO	Specialist: Tyler, George		Agreement Number:
Airport ID: KBEH			Airport City: BENTON HARBOR		State: MI
Facility ID:	Facility Type:	Flight Inspection Remark Type: New FC Slot			
Procedure Comments: ACTIVE AIRNAV DATA UTILIZED FOR KBEH AND RWYS. VOR MON SUPPORTING ELX DECOMMISSIONING. THIS CANCELS T NOTAM FDC 5/4195. CRC REMAINDER CHANGED FROM 6B96D9F4 TO 94623AB8. CONTACT CASEY HILL, AJV-A412, 405-954-0624. 09/09/2025: THIS IS A CORRECTED COPY OF THE FORM APPROVED ON 07/26/2025. CORRECTED ALTIMETER SETTING LNAV/VNAV DA TO INCREASE FROM 1076 TO 1080. QUALITY 16 CHECKED QUALITY 29 CHECKED QUALITY 13 CHECKED					

WAAS CH 86912 W10A	APP CRS 094°	Rwy Ldg 6006 TDZE 631 Apt Elev 649
--	------------------------	---

RNAV (GPS) RWY 10
SOUTHWEST MICHIGAN RGNL (BEH)

RNP APCH - GPS.


▼

▲



Rwy 10 helicopter visibility reduction below ¾ SM NA. For uncompensated Baro-VNAV systems, LNAV/VNAV NA below -20°C or above 54°C. Baro-VNAV and VDP NA when using LWA altimeter setting. When local altimeter setting not received, use LWA altimeter setting: increase LPV DA to 917 feet and all visibilities ½ SM; increase LNAV/VNAV DA to 1076 feet and all visibilities ¼ SM; increase all MDAs 40 feet and LNAV visibility Cats C and D ¼ SM.

MISSED APPROACH:
Climb to 2500 direct
GIDPE and hold.

ASOS 121.55	SOUTH BEND APP CON* 118.55 257.8	CLNC DEL 119.7	UNICOM 123.0 (CTAF) 0
-----------------------	--	--------------------------	---------------------------------



ELEV 649	TDZE 631
----------	----------



CATEGORY	A	B	C	D
LPV DA		881-¾	250 (300-¾)	
LNAV/VNAV DA		1040-1½	409 (400-1½)	
LNAV MDA	1040-1	409 (400-1)	1040-1½	409 (400-1½)


REIL Rwy 10, 14 and 32 0

MIRL Rwy 14-32 0

MIRL Rwy 10-28 0

NM 9 18 27 36 45
FT 50000 100000 150000 200000 250000

AIRPORT ID: KBEH
AIRPORT NAME: SOUTHWEST MICHIGAN RGNL
CITY/STATE: BENTON HARBOR/MICHIGAN
PROC ID: RNAV (GPS) RWY 10
AMDT: 2
SCALE: 1:500,000
TAA ST-IN



Map of the Southwest Michigan region, centered on KBEH (Southwest Michigan Regional Airport). The map displays various airports, navigational aids, and terrain features. Key locations include Grand Haven, Holland, Zeeland, and Zeeland.

AIRPORT ID: KBEH
AIRPORT NAME: SOUTHWEST MICHIGAN RGNL
CITY/STATE: BENTON HARBOR/MICHIGAN
PROC ID: RNAV (GPS) RWY 10
AMDT: 2
SCALE: 1:500,000
TAA L BASE


Map Details:

- Class B Altitudes:** Indicated by a dashed red line and text "CLASS B ALTITUDES".
- Navigation Aids:** VOR stations are shown with callouts like "V 30", "V 170", "V 84", "V 100", "V 526".
- Obstacles:** Obstruction symbols with MSL and AGL altitudes are present, such as "1032 (353)", "1038 (348)", "1017 (340)".
- Geographic Features:** "LAKE MICHIGAN" is labeled in the bottom left.
- Other Airports:** "SOUTH HAVEN AREA RGNL (LWA)", "WATERLIET MUNI (40C)", "DOWAGIAC MUNI (C91)", "ANDREWS UNIVERSITY AIRPORT (C20)".
- Communication:** "TAA Left Base 184 CW 274 TOWER (1228) 26-000890" is noted in a red box.

TAA Left Base 184 CW 274
TOWER (1228)
26-000890

NM 8 16 24 32 40
FT 50000 100000 150000 200000 250000

AIRPORT ID: KBEH
AIRPORT NAME: SOUTHWEST MICHIGAN RGNL
CITY/STATE: BENTON HARBOR/MICHIGAN
PROC ID: RNAV (GPS) RWY 10
AMDT: 2
SCALE: 1:500,000
TAA R BASE



AIRPORT ID: KBEH
AIRPORT NAME: SOUTHWEST MICHIGAN RGNL
CITY/STATE: BENTON HARBOR/MICHIGAN
PROC ID: RNAV (GPS) RWY 10
AMDT: 2
SCALE: 1:500,000

