U.S. DEPARTMENT OF TRANSPORTATION - FEDERAL AVIATION ADMINISTRATION TAKEOFF MINIMUMS AND OBSTACLE DEPARTURE PROCEDURES (ODP)

Bearings, headings, courses, tracks and radials are magnetic. Elevation and altitudes are in feet MSL. Altitudes are minimum attitudes unless otherwise indicated. Cellings are in feet above airport elevation. Distances are in nautical miles. Visibilities are in statute miles or feet RVR unless otherwise indicated.

City, State	Airport	Effective Date	Amdt. No.
BLOOMINGTON, IN	MONROE COUNTY	25 AUG 2011	6

TAKEOFF MINIMUMS:

RWY 06, 17, 35, STANDARD

RWY 24, 300-1

TEXTUAL DEPARTURE PROCEDURES:

TAKEOFF OBSTACLE NOTES:

NOTE: RWY 06, POLES AND BUILDING BEGINNING 424 FT FROM DER, 332 FT LEFT OF CENTERLINE, UP TO 29 FT AGL/874 FT MSL. TREES BEGINNING 491 FT FROM DER, LEFT AND RIGHT OF CENTERLINE, UP TO 72 FT AGL/972 FT MSL. FENCE 181 FT FROM DER, 115 FT RIGHT OF CENTERLINE, 6 FT AGL/846 FT MSL. VEHICLE ON ROAD BEGINNING 89 FT ROM DER, LEFT AND RIGHT OF CENTERLINE, 15 FT AGL/862 FT MSL.

NOTE: RWY 17, VEHICLE ON ROAD 187 FT FROM DER, 18 FT RIGHT OF CENTERLINE, 15 FT AGL/850 FT MSL. TREE 1263 FT FROM DER, 625 FT RIGHT OF CENTERLINE, 32 FT AGL/871 FT MSL. BUSH 855 FT FROM DER, 594 FT LEFT OF CENTERLINE, 25 FT AGL/862 FT MSL.

NOTE: RWY 24, TREES AND POLES BEGINNING 158 FT FROM DER, LEFT AND RIGHT OF CENTERLINE, UP TO 85 FT AGL/1021 FT MSL. FENCE 394 FT FROM DER, 72 FT LEFT OF CENTERLINE, 9 FT AGL/849 FT MSL. BUILDINGS BEGINNING 1990 FT FROM DER, 321 FT RIGHT OF CENTERLINE, UP TO 25 FT AGL/952 FT MSL. VEHICLE ON ROAD BEGINNING 45 FT FROM DER, LEFT AND RIGHT OF CENTERLINE, 15 FT AGL/945 FT MSL.

NOTE: RWY 35, TREES BEGINNING 2119 FT FROM DER, 120 FT LEFT AND RIGHT OF CENTERLINE, UP TO 85 FT AGL/975 FT MSL.

CONTROLLING OBSTACLES:

RWY 24, 1021 FT TREE 390812.87N/0863754.37W; 1015 FT TREE 390759.61N/0863744.12W.