

PREPARED BY THE PRODUCT SUPPORT GROUP, AJV-34

By amending: §97.23 VOR, VOR/DME, VOR or TACAN, and VOR/DME or TACAN; §97.25 LOC, LOC/DME, LDA, LDA/DME, SDF, SDF/DME; §97.27 NDB, NDB/DME; §97.29 ILS, ILS/DME, MLS, MLS/DME, MLS/RNAV; §97.31 RADAR SIAPs; §97.33 RNAV SIAPs; and §97.35 COPTER SIAPs, Identified as follows:EFFECTIVE UPON PUBLICATION						
AIRAC DATE	STATE	CITY	AIRPORT	FDC NUMBER	FDC DATE	SUBJECT
10-Jan-13	MT	Poplar	Poplar Muni	2/4971	11/26/12	TAKEOFF MINIMUMS AND (OBSTACLE) DP, Orig

FDC 2/4971 PO1 FI/P ODP POPLAR MUNI, POPLAR, MT. TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES ORIG...
 ADD TAKEOFF MINIMUMS: RWY 2/20 NA - ATC. CHANGE TAKEOFF OBSTACLE NOTES TO READ: NOTE: RWY 09, LT SUPPORT STRUCTURE 10 FT FROM DER, 18 FT RIGHT OF CENTERLINE, 2 FT AGL/2038 FT MSL. FENCE 24 FT FROM DER, 344 FT LEFT OF CENTERLINE, 10 FT AGL/2046 FT MSL. TERRAIN 26 FT FROM DER, 492 FT LEFT OF CENTERLINE, 2037 FT MSL. TREE 504 FT FROM DER, 483 FT LEFT OF CENTERLINE, 40 FT AGL/2080 FT MSL. POLE 1175 FT FROM DER, 756 FT RIGHT OF CENTERLINE, 31 FT AGL/2067 FT MSL. POLE 1233 FT FROM DER, 619 FT LEFT OF CENTERLINE, 32 FT AGL/2068 FT MSL. POLE 1423 FT FROM DER, 618 FT RIGHT OF CENTERLINE, 38 FT AGL/2074 FT MSL. POLE 1742 FT FROM DER, 593 FT RIGHT OF CENTERLINE, 45 FT AGL/2081 FT MSL. NOTE: RWY 27, LT SUPPORT STRUCTURE 10 FT FROM DER, 17 FT LEFT OF CENTERLINE, 2 FT AGL/2027 FT MSL. FENCE 65 FT FROM DER, 341 FT RIGHT OF CENTERLINE, 4 FT AGL/2029 FT MSL. TREE 248 FT FROM DER, 497 FT RIGHT OF CENTERLINE, 21 FT AGL/2047 FT MSL. THIS IS TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES, ORIG-A.