



APP CRS	Rwy Ldg	9000
123°	TDZE	617
	Apt Elev	617

RNAV (RNP) Z RWY 11

ST LOUIS LAMBERT INTL (STL)

RNP AR APCH - GPS, min RNP 0.30. Authorization required from HRBEE or RRIPP: RF.				ALSF-2 	MISSED APPROACH: Climb to 1100 then climbing right turn to 3000 direct IMPER and hold.	
RADAR required for procedure entry.						
Simultaneous approach authorized with Rwy 12L/R, except for arrivals at RRIPP and HRBEE. Use of FD or AP providing RNAV track guidance required during simultaneous operations. For uncompensated Baro-VNAV systems, procedure NA below -16°C or above 54°C. For inop ALS, increase RNP 0.30 all Cats visibility to RVR 4500.						
D-ATIS 125.025 379.925	ST. LOUIS APP CON 132.125 360.6	ST. LOUIS TOWER 132.475 239.275	GND CON 121.9 348.6 (Inbound) 121.65 377.175 (Outbound) 118.925 227.125 (Rwy 11/29)	CLNC DEL 119.5 363.1	CPDLC	



VGS1 and RNAV glidepath not coincident (VGS1 Angle 3.00/TCH 67).			
MUDYY	WATRR	1100	3000
1900	1700	IMPER	
GP 3.00°			
TCH 59			
0.9 NM	3.2 NM		
CATEGORY	A	B	C
RNP 0.30	DA	925/24	308 (400-1/2)
AUTHORIZATION REQUIRED			