

WAAS CH 90225 W05A	APP CRS 048°	Rwy Idg 4589 TDZE 45 Apt Elev 45
--	------------------------	---

RNAV (GPS) RWY 5

NUIQSUT (AQT) (PAQT)

⚠ Inoperative table does not apply. For uncompensated Baro-VNAV systems, LNAV/VNAV NA below -25°C (-13°F) or above 54°C (130°F). DME/DME RNP-0.3 NA. When local altimeter setting not received, use Deadhorse altimeter setting and increase all DA 123 feet and all MDA 140 feet, increase LPV all Cats, LNAV/VNAV all Cats, and Circling Cat C visibility ¼ mile, increase LNAV Cat C visibility ½ mile. VDP and Baro-VNAV NA with Deadhorse altimeter setting.


MALSF




MISSED APPROACH.
Climb to 1700 direct
JQUQU and hold.

ASOS 135.35	ANCHORAGE CENTER 119.4	DEADHORSE RADIO 122.5	CTAF 122.8
-----------------------	----------------------------------	---------------------------------	----------------------

Procedure NA for arrivals at CEDUN on G16 westbound.




Procedure NA for arrivals at
ZADRO on G16 northeast bound.




ELEV 45		TDZE 45
---------	--	---------

VGSI and RNAV glidepath not coincident (VGSI Angle 3.00/TCH 33).



CATEGORY	A	B	C	D
LPV DA	295-1 250 (300-1)			NA
RNAV/ VNAV DA	295-1 250 (300-1)			NA
RNAV MDA	440-1 395 (400-1)		440-1 $\frac{1}{8}$ 395 (400-1 $\frac{1}{8}$)	NA
CIRCLING	520-1 475 (500-1)		520-1 $\frac{1}{2}$ 475 (500-1 $\frac{1}{2}$)	NA



MIRL Rwy 5-23 **L**
REIL Rwy 23 **L**