New Runway Construction/Opening

Start date:

		Required	Status	Date Complete	Reason Not Accomplished
	As Early as Possible:			-	
1	Review best practices/lessons learned	Х			
2	Notify local Technical Operations System Support Center (SSC) of proposed start and end dates to begin NAVAIDs evaluation for impact and to begin the Strategic Event Coordination (SEC) for NAVAID shutdown during construction	X			
3	Review airport Master Plan (long-range) with airport authority Review specific imminent phases (revisit as funding changes); request daily updates be posted on airport authority webpage	X			
4	Notify the Airport Construction Advisory Council via email to the following address: 9-AJA-ConstructionCouncil@faa.gov	X			
5	Coordinate opening coincidental to publication/charting date with sponsor Published Departure/Arrival instrument procedures take 18-24 months Airfield Diagram depictions or AFD descriptions prior to runway opening date will require issuing NOTAMs	Best Practice			
6	Conduct and complete SMS activities (SRMD, SRMDM, etc.)	Х			
7	Develop plans for modeling the new runway operations in the simulator	X			
8	Advise/coordinate project with regional Runway Safety Office - accomplish local-regional RSAT focused on construction impact	Х			
9	Tailor communication strategy to this project	Х			
10	Coordinate with Traffic Management - develop impact statement	Х			
11	Confirm effect to instrument procedures, critical areas, protected surfaces; check with AFS	Х			
12	Review necessary LOA changes related to local operators	Х			
13	Determine extent of changes needed for all Orders, Notices, LOA's, binders	Х			
14	Evaluate whether construction may generate need for new/different runway hot spot(s)	Х			
15	Review ARFF routes/staging and suspicious materials holding areas with airport authority	Х			
16	Confirm location of RSA(s) for each proposed and existing runway affected	Х			
17	Determine extent of surface surveillance (ASDE-X and/or AMASS) map changes needed and coordinate as necessary Allow sufficient time for Program Office (MMAC) response	Х			
18	Determine timing of video mapset change and coordinate as necessary	Х			

Page 1 as of: Mar. 2014

		Danninad	04-4	Data	December Assemblished
		Required	Status	Date Complete	Reason Not Accomplished
19	Review Construction Safety Phasing Plan (CSPP) with Airport District Office	Х		Complete	
	(ADO); the ADO should notify the Planning & Requirements (P&R) office at	^			
	the Service Center via a determination letter, per the Strategic Event				
	Coordination national service level agreement				
	Review construction safety plans submitted to ADO and comment on				
	vehicle routes to/from movement areas; insist on use of access roads to				
20	runway ends if construction affects intersecting runways Review movement area visibility changes caused by construction	Х			
21	Coordinate and draft amended Movement Area LOA as necessary	X			
22	Review runway/taxiway marking/signage changes with airport authority	X			
	cross-check that edge/centerline lights on closed (new) runway can be	^			
	activated when construction completes				
	request hard-wired (long-duration) lighted "X's" to avoid fuel starvation				
	Get Runway Safety involved				
23	Review planned nighttime lighting to ensure tower & pilot vision is not	Х			
24	Obstructed Device LAUSO changes that are passesser.	X			
24	Review LAHSO changes that are necessary Coordinate changes with airport authority; may require markings, signage,	^			
	and lighting				
25	Review ADW and CRDA changes that are necessary	Х			
	If arrival tools are to be used, make sure automation and radar maps are				
	updated				
26	Initiate request with AJV to amend airport diagram	X			
27	Create, approve, and publish changes to local procedures (SOP)	X			
28	Notify carriers/operators of any changes in instrument procedures &	Х			
	planned impacts Lighted "X's" should be placed to prevent runway use;				
	Edge/centerline lights on new runway should be disabled (covered) until				
	commissioning				
29	Conduct initial briefing to operational personnel to raise their situational	Х			
	awareness				
30	Anticipate runway/taxiway name changes (see Best Practices)	X			
31	Confirm points-of-contact for tactical construction/crane operations	X			
32	Brief controllers/operational personnel (first briefing on specific project)	Х			
i					

Page 2 as of: Mar. 2014

		D	01-1	D-1	December 1
		Required	Status	Date	Reason Not Accomplished
	Within 20 Days of Drainet Clark			Complete	
	Within 30 Days of Project Start				
33	Confirm airport diagram change publication New diagram changes can require more than 60-days if survey information is not available; communicate to AJV office early to avoid charting issues - Jeppesen (especially); Garmin, LIDO, Maptech, too AIM (Christopher Criswell – FAA lead) will confirm - do not call chart/map vendors directly	X			
34	Contact AIM (AJV-3) to coordinate digital Construction Notice, (diagram showing closures); on a trial basis (largely determined by availability of GIS data); diagrams are not associated with formal AIM (AJV-3) (Aeronav) publication cycle	Best Practice			
35	Confirm points-of-contact for tactical construction/crane operations Ensure barricade placement matches NOTAMs and other operational restrictions during construction	X			
36	Conduct facility controller awareness campaign Posters, FLM crew briefings, etc. initiated NLT 2 weeks before closure	Х			
37	Conduct pilot awareness campaign; (i.e., INFo message, FAAST message) Schedule an RSAT at a minimum (Summit for Core-30 airports) approximately 30 days before closure; Letter to Airmen developed and posted	Х			
38	Develop cheat-sheets for tower-cab that includes Closed Areas and Vehicle Flows	Х			
39	Complete simulator and classroom training	Х			
40	Brief controllers/operational personnel (first briefing on specific project)	Х			
	Within 2 Weeks of Project Start				
41	Brief FLMs/OMs/CICs on ATIS review requirements refresher	Х			
	On Day of Opening				
42	Re-brief controllers/operational personnel	Х			
43	Stage project knowledgeable staff personnel in operating quarters (day and night shifts)	X			
44	ATIS software checked to ensure information is broadcast digitally through ARINC	Х			
45	Check ATIS content on TDLS	X			
46	Verify NOTAMs in place; review for accuracy Ensure barricade placement matches NOTAMs and other operational restrictions	Х			
47	Implement changes to surface surveillance (ASDE-X and/or AMASS) maps	Х			

Page 3 as of: Mar. 2014

		Required	Status	Date Complete	Reason Not Accomplished
48	Implement Movement Area LOA	Х		•	
49	Make necessary changes to IDS-4	Х			
50	Verify lighted "X's" are removed from runway ends;	Х			
	Ensure that edge/centerline lights on closed section of runway/taxiway are				
	restored				
51	Update all Orders, Notices, LOA's, binders as needed	X			
52	JUST SAY "NO" - no last minute changes If airport (or contractor) fails to abide by the agreed phasing, FAA should request immediate meeting with airport sponsor; Consider suspending operations when "radio-out" (lost communications) with vehicle (or aircraft) occurs in construction movement area	X			
	During Construction				
53	Re-check all websites: (Runway Safety, airport authority, etc.) - ensure they stay current	Х			
54	Recheck NOTAMs and ATIS constantly; review for accuracy Advise airport authority of any NOTAM discrepancies; have separate person review ATIS recordings	Х			
	Following Construction				
55	Report out to the District Manager, Service Area Director, & Airport Construction Advisory Council (ACAC)	Х			
56	Conduct surveys targeted at reviewing construction activities and mitigations to determine effectiveness of new procedures Adverse trends and/or unsafe findings are reported to the ACAC	Х			

Notes/	comments:
--------	-----------

Page 4 as of: Mar. 2014