

Remote Tower Services (RTS)

Andras Kovacs

Manager, NextGen Tech Development & Prototyping, Surveillance Branch, ANG-C52



Agenda

- Overarching Remote Tower Services
- Leesburg Remote Tower
- Fort Collins Remote Tower
- FY18 Congressional Appropriation for Remote Towers







OVERARCHING REMOTE TOWER SERVICES

Remote Tower Services (RTS) in the NAS

OVERARCHING RTS - FAA EXECUTIVE COUNCIL GOAL

- Establish non-federal certification strategy to allow for RTS in NAS at Sponsor-Owned FAA Contract Tower (FCT) airports
 - **Establish Remote Tower Service Levels.** Bundle existing tower operation services to create RTS Service Levels and identify RTS standards for each Service Level.
 - Qualified Vendor/System Approval Process. Develop process to implement, evaluate, and certify non-federal vendor systems for RTS Service Levels.



Remote Tower Displays of Airfield w/ Controller positions

ONGOING SITE SPECIFIC ACTIVITIES

- Leesburg Remote Tower
 - FAA collaborates with SAAB and the Commonwealth of Virginia to develop an evaluation process which is designed to reach a decision on operational approval for their remote tower system at Leesburg Executive Airport (JYO) only.
 - SAAB funded effort with FAA providing internal Subject Matter Expertise
- Fort Collins Remote Tower
 - FAA collaborates with the State of Colorado to select and evaluate a Remote Tower system at Northern Colorado Regional Airport (FNL). The goal is to determine if provision of Class D air traffic control tower services can be provided safely and efficiently by a tower controller using Remote Tower technologies instead of the traditional Out-The-Window (OTW) view of a tower cab.
 - Colorado Department of Transportation (CDOT) funded effort with FAA
 providing Subject Matter Expertise



Airfield Camera Housing



Tower Funding Types

Legend

FAA costs

 \bigcirc

Non-FAA costs

FAA Share of Funding

Tower Funding Type		Tower Construction, Equipment, and Maintenance	Controller Staff	Number of Airports > 40 Years Old / Total	Number with Union Rep.* / Total
FAA-staffed Tower				103/264	264/264
FAA Contract Tower (FCT)	FAA-owned	Technical Operations Service Area Office		80/102	34/102
	FAA-owned (Cost Share)	Technical Operations Service Area Office	Capped at 20%	3/3	1/3
	Sponsor- owned	FAA Pays for FAA owned and operated equipment as well as training for government furnished equipment		66/135	51/135
	Sponsor- owned (Cost share)	FAA Pays for FAA owned and operated equipment as well as training for government furnished equipment	Capped at 20%	9/13	6/13



Sources:

Order JO 7210.54B FAA Contract Tower (FCT) Operation and Administration (October 1, 2006); updated version C does not describe cost share arrangements. 49 U.S. Code § 47124 - Agreements for State and local operation of airport facilities



Working Service Level (SL) Framework

Current Model

Physical tower - Class D



- "ALL" refers to airport ATM services provided by the tower controller
- Excludes radar separation services
- Airborne IFR separation is provided by overlying IFR facility



None



Proposed Model

Physical or Remote Tower - Airspace Class varies by SL

ATCT with Radar Services

- ATCT Service provided by a CPC in accordance with JO 7110.65 and other Orders
- Pilot participation in accordance with the FAR

Radar Separation, Control, Advisory, & Information Services – 25/25

 Visual observation of the airfield augmented <u>with</u> secondary surveillance source used to provide radar services

ATCT Services - Mode A

- ATCT Service provided by a CPC in accordance with JO 7110.65 and other Orders
- · Pilot participation in accordance with the FAR

Control, Advisory & Information Services – 24/25

 Visual observation of the airfield augmented <u>with</u> secondary surveillance source for situational awareness only (not used to provide radar services)

ATCT Services - Mode B

- ATCT Service provided by a Certified Professional Controller (CPC) in accordance with JO 7110.65 and other Orders
- Pilot participation in accordance with the FAR

- Visual observation of the airfield augmented <u>without</u> secondary surveillance source
- Lack of secondary surveillance source may result in the implementation of site-specific ATC procedures

Airport Advisory Services - Mode A

- Airport advisory services provided by certified Specialist in accordance with JO 7110.10 and other Orders
- Voluntary pilot participation

Advisory & Information Services – 14/25

- Airport advisory services provided <u>with</u> visual observation of the airfield
- Traffic information about observed, known, or reported traffic

Airport Advisory Services - Mode B

- Airport advisory services provided by certified Specialist in accordance with JO 7110.10 and other Orders
- Voluntary pilot participation

- Airport advisory services provided <u>without</u> visual observation of the airfield required
- Traffic information about known or reported traffic

Airport Information Services

- · No special personnel certification required
- Voluntary pilot participation
- Can be automation based


- Information Services 3/25
- Airport information services provided without visual observation of the airfield required
- Notes: 1) These airport ATM service levels are distinct from ATC facility levels and the Navigation Service Groups
 - 2) IFR separation services are delivered by overlying IFR facility in the SLs without Radar Services
 - 3) Each SL has the equipment from SLs that precede it
 - 4) Remote Tower services may or may not be applicable/business viable to deliver Airport Advisory or Airport Information Service Levels





LEESBURG REMOTE TOWER

Leesburg RTS Status Sequence of Events



Complete On Track



Timeframe: Summer '19


Leesburg RTS Status

- Since 2016, FAA completed series of passive tests and Safety Panels investigating RTS hazards and risks, building up to Active Testing
- Active RTS testing completed Jun-Sep 2017
 - Actively controlled 5500+ aircraft and 500+ ground movements over 3.5 months under varying traffic loads, traffic patterns and weather conditions
- Held Safety Risk Management Panel in Nov 2017
 - Investigated hazards/risks associated with moving into Phase 3a Industry-Led Initial
 Operating Capability (IOC) operation
 - Established Industry-Led IOC operational terms and associated safety risk validation processes with JYO airport, contract controllers and vendor
- Initiated Industry-Led IOC capability on June 25, 2018
 - IOC IS EXTENDED ASSESSMENT & VALIDATION OF THE REMOTE TOWER SYSTEM
 - Airport Traffic Control Tower (ATCT) services provided 7 days/week, 14 hours/day
 - Remote Tower is applying Site-Specific Standard Operating Procedures (SOPs) fully coordinating with adjacent facilities (Potomac TRACON and Dulles Tower)
 - No limitations placed on number of aircraft





Phase 3 Overview







Leesburg RTS Phase 3a – Industry Led Initial Operating Capability (IOC)

Purpose:

- Operate Remote Tower with existing array of functions and capabilities in its current location, applying Site-Specific Standard Operating Procedures (SOPs)
- Validate safety requirement
- Validate Remote Tower Service Level (Mode B) needs and gain valuable insight and data contributing toward future standardization efforts

Logistics:

- Airport Traffic Control Tower (ATCT) services provided 7 days/week, 14 hours/day, with a staff of three (3) controllers at all times for approximately 1 year
- During the first five weeks of Phase 3a:
 - Mobile Airport Traffic Control Tower (MATCT) was staffed to maintain situational awareness and intervene as necessary to ensure safety
 - Remote Tower was only used 5 days/week, 8 hours/day with FAA personnel present



Leesburg RTS Phase 3b – Industry-Led Initial Operating Capability (IOC) – Additional Evaluation

Purpose:

- Further evaluate the Leesburg RTS under degraded mode operation (e.g., loss of a screen display or camera) in its current location
- Evaluate consolidation of controller positions in its current location
- Validate Remote Tower Service Level needs and gain valuable data toward future standardization efforts

Logistics:

- ATCT services provided for a pre-determined number of days and number of hours per day
- ATCT services provided by MATCT and rTWR during set periods –
 Details still to be determined





Leesburg RTS Phase 3c – Industry Led Initial Operating Capability (IOC) with potential system improvements

Purpose:

- Operate the Leesburg RTS with added system capabilities (e.g., RADAR) in its new location
- Allow for added redundancy to Leesburg RTS
- Validate added system improvements to reduce or eliminate existing safety controls from Phase 3a (Site-Specific SOPs)
- Validate Remote Tower Service Level (Mode A) needs and gain valuable insight and data toward future standardization efforts

Logistics:

 ATCT services provided for a pre-determined number of days and number of hours per day








FORT COLLINS REMOTE TOWER

Fort Collins RTS Status Planned Sequence of Events





Fort Collins RTS Status

Contract Establishment – Completed

- Nov. 2016: Fort Collins RTS Request for Information (RFI) posted
- Jul. 2017: FAA and Searidge Technologies (SRT) Sign an OTA

Site Engineering & System Design Activities – Completed


- Oct. 2017: Solicited Construction Bid, Developed Integrated Schedule
- Dec. 2017 Jan. 2018: Vendor finalized FNL System Design, Drafted Concept of Operations Document
- Jan. Apr. 2018: Vendor completed Site Engineering Report, Conducted Industry-led Factory Acceptance Test (FAT)

System Installation/Optimization Activities – Ongoing

- Summer 2018: Complete Site Engineering and System Installation
- Summer / Fall 2018: Conduct FNL Remote Tower system optimization,

Evaluation Activities – Upcoming

- Fall 2018: Conduct FNL Remote Tower system shakedown (Phase 0 eval)
- Fall 2018 / Winter 2019: Conduct initial Safety Risk Assessment (SRA) of the FNL Remote Tower system







FY18 CONGRESSIONAL APPROPRIATION FOR REMOTE TOWERS

2018 Congressional Appropriation

"Remote Towers. – The agreement includes \$5,000,000 to continue the ongoing remote tower project, including operating costs, and to deploy and pilot remote tower systems to at least two additional airports. The FAA is directed to begin the remote tower pilot initiative within 45 days of enactment of this act."





RTS Plan responding to 2018 Congressional Appropriation

- Complete activities at Existing Site (Leesburg)¹
 - Complete Evaluation / Certification Activities
- Issue RFIs searching for airport/vendor/ANSP teaming arrangements via Other Transaction Agreement (OTA) to begin deploying Remote Tower services at 2 additional sites
 - Focus on Sponsor-owned FAA Contract Tower (FCT) airports with aging tower infrastructure²
 - Validate Remote Tower Business Case
 - Explore true Remote Tower configurations with Remote Tower Center located offairport
 - Expand the Qualified Vendor System List to other vendors and/or yet unexplored
 Service Level categories

CONSIDERATIONS / NOTES:

- ¹Remote Tower business case not yet proven
- ² Vendors actively engaging airports with Sponsor-owned FCTs now



